

Township 3 N., R.37 E,W.M.

Chains	N.33' E. on E. Bdy. of Sec. 24
40.00	A point 22lks. W. of $\frac{1}{4}$ Sec. Cor., which is A Stone ^{marked} amrked and witnessed. The true course of this line is N.52' E.40.00 chs. Thence I run
	N. 52' E. on E. Bdy. of Sec. 24
38.07	A point, 7 lks. W. of Cor. of Secs.13 and 24. Post and mound of stone as described by the Surveyor- General. True course of this line N.58' E.,3807 chs. Land;mountainous. Soil;poor,rocky 4th rate. Timber; fir, spruce and tamarack. Dense undergrowth, willow and alder. Mountainous land, 78.07 chs.
	N.58' E. on E. Bdy. of Sec. 13
39.90	A point 48 lks. E. of $\frac{1}{4}$ Sec. Cor., a stone,marked,as de- scribed by the Surveyor General. True course of line N.17' E. 39.90 chs. N.17' E. along E. Bdy. Sec. 13.
40.09	A point 42 lks. W. of Cor. of Secs.12 & 13,which is a Stone, marked and witnessed as described by the Surveyor veyor-General. True course of line N,53' E., 40.09 chs. Land; mountainous. Soil; poor 4th rate. Timber; fir and scattering pine. Dense undergrowth, willow, 43.00 chs. Mountainous 79.99 chs.
	N.53' E. on E. Bdy. of Sec. 12.
39.75	A point, 24 lks. E. of $\frac{1}{4}$ Sec. Cor., which is a tree Cor., marked and witnessed as described by the Sur- veyor-General. True course of line N.32°6', 39.75 chs. N,32' E. along E. Bdy. of Sec. 12.
39.35	A point, 32 lks. W. of Cor. of Secs.1 & 12,