

South Bdy. Tp.3 N.,R.38 E. W.M.

Chains 40.00	Set spruce post on S.E. slope for $\frac{1}{4}$ Sec. Cor. A spruce, 16 ins. diam., brs. N.30°W., 10 lks. dist. A pine, 18 ins. diam., brs. S.38° W., 64 lks. dist.	
45.00	Begin descent of the N.E. mountain side.	
80.00	Set pine post on the N.E. face of mountain for Cor. to Secs. 33, 34, 3 and 4. A fir, 30 ins. diam., brs. N.72° E., 44 lks. dist. A spruce, 22 ins. diam., brs. S.20° E. 80 lks. dist. A spruce, 24 ins. diam., brs. S.14° W., 63 lks. dist. A fir, 20 ins. diam., brs. N.36° W., 76 lks. dist. Land; surface mountainous. Soil; 3rd rate. Timber; heavy, pine, spruce, tamarack and fir.	-200
	East on the S. Bdy. of Sec. 34 Var. 22° 30' E.	
14.50	Brook, 15 lks. wide, course S.E.	-300
19.50	Same " " " East	
32.00	Leave brook, course N.80° E.	
40.00	Set Basalt Stone, 12 x 10 x 5 on steep N. hillside for $\frac{1}{4}$ Sec. Cor. A fir, 8 ins. diam., brs. N.52° E., 43 lks. dist. A spruce, 20 ins. diam., brs. S.74°W., 64 lks. dist.	
46.00	Same brook, course S.E.	-100
72.00	Leave timber, course N.W. & S.E.	
80.00	Set Basalt Stone, 18 x 10 x 5 on S. face of mountain in mound of stone for Cor. to Secs. 34, 35, 2 & 3. Drove stake and raised mound of stone in lieu of pits. Land; mountainous. Soil; 3rd rate. Timber; heavy on W. 72 chs., pine, fir, tamarack and spruce. June 7th, 1879.	
	East on the S. Bdy. of Sec. 35 Var. 19° 30' E.	
9.00	On spur, extending S.	+200