

## Subdivisional Lines T.3 N., R.38 E., W.M.

Chains	<p>2 ft. base, 1½ ft. high, W. of Cor. Pits impracticable.          From this Cor., the old Sec. Cor., a post with mound and          pits brs. N. 448 lks. dist. I destroy Cor. and mound.          Land; mountainous.          Soil; 3rd rate.          Timber; fir, pine and tamarack.          Undergrowth; alder, willow and small pine and spruce          groves.          Mountainous land, 80.00 chs.</p>
	Sept. 2, 1903
40.00	<p>N. 3' W. bet. Secs. 3 &amp; 4.          Set tamarack post, 3 ft. long, 3 ins. sq., 24 ins. in the          ground, for ¼ Sec. Cor., marked ¼ S 4 on W., S 3 on E.          faces, from which,              A pine, 5 ins. diam., brs. N.64° E., 78 lks. dist.              marked ¼ S 3, B.T.              A pine, 3 ins. diam., brs. N.31° W., 46 lks. dist.,              marked ¼ S 4, B.T.          From this point, the old ¼ Sec. Cor., a post, marked and          witnessed, brs. N. 447 lks. dist. I destroy Cor. and          marks on bearing trees.</p>
70.21	<p>Intersect N. Bdy. of the Tp. 325 lks. W. of the ¼ Sec. Cor. <sup>50</sup>          on S. Bdy. of Secs. 34, T 4 N., R 38 E. at intersection,          a fir, 7 ins. diam., for closing Cor. of Secs. 3 and 4.          I mark CC, T3N., R38 E., on S. face, S3 on E., S4 on W.          sides, from which,              A spruce, 9 ins. diam., brs. S.45° E., 25 lks. dist.,              marked T.3 N., R.38 E., S.3, B.T.              A fir, 8 ins. diam., brs., S.51° W., 83 lks. dist.,              marked T.3 N., R.38 E., S.4, B.T.          From this Cor., the old closing Cor., a tree, marked and          witnessed, brs. W. 30 lks. dist. I destroy marks on Cor.          and bearing trees.          Land; mountainous.          Soil; 3rd rate.          Timber; fir, spruce and willow.</p>