

Retracement S. Bdy., T.4 N., R.38 E., W. M.

Chains		Feet
	<p>Timber; fir, spruce & tamarack. Dense undergrowth; alder & willow. Mountainous land, 80.00 chs. Sept. 7, 1903.</p>	
	<p>Retracement of S. Bdy., T.3 N., R.38 E., W. M. As surveyed by same U.S. Deputy Surveyor, Under same Contract and date.</p>	
	<p>From the established Closing Cor., T.2 N., Rs. 37 & 38 E., which is a post, marked & witnessed as described by the Surveyor General.</p>	
	<p>I run W. bet. Secs. 1 & 31.</p>	
10.00	<p>Spring branch, 2 lks. wide, course N.</p>	
45.97	<p>The Closing Cor. of T.3 N., R.38 E., on W. Bdy. of Tp. & 655 lks. N. of established Cor., T.3 N., R.37 E., a stone, marked & witnessed as described by the Surveyor General.</p>	
	<p>The Closing Cor. is a basalt stone, 20 x 12 x 7 ins., 12 ins. in ground, for Closing Cor., T. 3 N., R.38 E., marked C.C., T.3 N., R.38 E. on E. side with 6 grooves on N. & E. faces, from which, A fir, 28 ins. diam., brs. N.31°E., 175 lks. dist., marked C.C., T.3 N., R.38 E., S.31, B.T.</p>	
	<p>Land; mountainous. Soil; 2nd rate. Timber; fir & tamarack. Dense undergrowth; willow & alder.</p>	
	<p>Mountainous land, heavily timbered & dense undergrowth, 45.97 chs.</p>	
	<p>Retracement S. Bdy., T.4 N., R.38 E., W. M. As surveyed by same surveyor, under same Contract & date.</p>	
	<p>From the established Cor. to Secs. 32 & 33, on S. Bdy., T. 4 N., R.38 E.</p>	
	<p>I run W. on blank line on S. Bdy., Sec. 32.</p>	
40.75	<p>A point, 33 lks. S. of $\frac{1}{2}$ Sec. Cor.</p>	
81.00	<p>A point, 80 lks. S. of Cor. to Secs. 31 & 32 & at</p>	
121.75	<p>A point, 117 lks. S. of $\frac{1}{2}$ Secs. Cor. on S. Bdy., Sec.31.</p>	