


Retracement of 3 Subdivision  $\frac{1}{2}$  Miles in T 3 N R 38 E.

Chains	
	<p>A pine, 10 ins. diam., brs. S.23<math>\frac{1}{2}</math>°E., 51 lks. dist., marked T 3 N R 38 E S 4 C C B T.</p> <p>A pine, 8 ins. diam., brs. S.75<math>\frac{1}{2}</math>°W., 26 lks. dist., marked T 3 N R 38 E S 5 C C B T.</p> <p>From point of intersection the <math>\frac{1}{4}</math> Sec. Cor. of Sec.33 only, brs. N.89°55'E., 2.85 chs. dist.; heretofore described.</p> <p>Land; rolling.</p> <p>Soil; sandy loam, 2nd rate.</p> <p>Timber; fir, pine, spruce and tamarack.</p> <p>Undergrowth; alder, huckleberry, vinemaple, and willow.</p>
	<p>The <math>\frac{1}{4}</math> Sec. Cor. of Secs. 5 and 6, determined by reference to the record bearing and distance to one of the original bearing trees.</p> <p>At point for Cor.</p> <p>Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, for <math>\frac{1}{4}</math> Sec. Cor., with brass cap marked</p> <div style="text-align: center;">  <p>S 6   S 5 1939</p> </div> <p style="text-align: right;">from which</p> <p>A spruce, 18 ins. diam., brs. E., 29 lks. dist., marked <math>\frac{1}{4}</math> S 5 B T. (Old B. T.)</p> <p>A spruce, 14 ins. diam., brs. N.84°W., 20 lks. dist., marked <math>\frac{1}{4}</math> S 6 B T. (New B.T.)</p> <p>Thence</p> <p>N.1°02'W., on true line bet. Secs. 5 and 6.</p> <p>Over rolling land, through heavy timber and dense undergrowth.</p> <p>0.15 Spring branch, 2 lks. wide, course N.70°E.</p> <p>10.00 Enter swamp, brs. E. &amp; W.</p> <p>19.40 Leave swamp, brs. E. &amp; W.</p> <p>20.75 Dirt road, brs. N.E. &amp; S.W.</p> <p>29.71 The original Closing Cor. of Secs. 5 and 6, determined by reference to the record bearings and distances to the original bearing trees; from which</p> <p>A fir, 14 ins. diam., brs. S.75°E., 26 lks. dist., marks grown over. (Old B.T.)</p> <p>A spruce, 16 ins. diam., brs. S.29°W., 33 lks. dist., marks grown over. (Old B.T.)</p>