

Retracement of 3 Subdivision $\frac{1}{2}$ Miles in T 3 N R 38 E W M.

Chains

I leave the two bearing trees intact for accessories to the new Closing Cor. of Secs. 5 and 6.

29.76 Intersect the S. Bdy. of T 4 N R 38 E.

Set an iron post, 3 ft. long, 2 ins. diam., 27 ins. in the ground, for Closing Cor. of Secs. 5 and 6, with brass cap marked

T4NR38E	
S32	
S 6	S 5
T3N	R38E
C C	
1939	

from which

A fir, 14 ins. diam., brs. S.65°E., 32 lks. dist., marks grown over. (Old B.T.)

A spruce, 16 ins. diam., brs. S.26 $\frac{1}{2}$ °W., 39 lks. dist., marks grown over. (Old B.T.)

From point of intersection the $\frac{1}{2}$ Sec. Cor. of Sec. 32 only, brs. S.89°40'E., 1.96 chs. dist., heretofore described.

Land; rolling.

Soil; sandy loam, 2nd rate.

Timber; fir, pine, spruce and tamarack.

Undergrowth; alder, willow, vinemaple and huckleberry.
