

East Bdy of T. 3 S. R. 29 E. W. M.
 Surveyed by George Williams, Deputy Surveyor
 Under Contract No. 176. Dated July 20, 1872.

Chains	
	North on a random line on the E. Bdys. Secs. 36, 25, 24, 13, 12 and 1. Var. 21° 10' E.
	I set temporary half mile and mile stones at every 40 and 80 chains and at 5 miles and 78 chs. to a point 1 Ch. 92 Lks. W. from the corner to T. 2 and 3 S. of Rs. 29 and 30 E. from which cor. I run.
	S. 14' W. on a true line along the E. Bdy. of Sec. 1. Var. 19° 15' E.
15.75	Cross hollow leading toward Griffiths' Sheep Ranch.
38.00	Set stone 18 x 10 x 6 for $\frac{1}{2}$ Sec. Cor.
78.00	Set stone 20 x 10 x 5 for cor. Secs. 1, 12, 6, 7 on W. Slope of hill. Land; rolling and broken.
	South 14' W. on a true line along the E. Bdy. of Sec. 12. Var. 24° 20' E.
6.00	Cross shallow gulch.
40.00	Set stone 25 x 10 x 4 for $\frac{1}{2}$ Sec. Cor.
80.00	Set stone 25 x 8 x 6 for cor. to Secs. 12 and 13 on N. side of hill from which a high round top-iron-rock butte bears N. 19° 30' E. dist. about 35 chs. Land; broken and hilly.
	S. 14' W. on a true line along the E. Bdy. of Sec. 13. Var. 20° E.
10.00	Top of hill.
40.00	Set stone 20 x 9 x 5 for $\frac{1}{2}$ Sec. Cor. on W. Slope of high hill.
58.00	Top of hill.
76.50	Cross gulch.
80.00	Set stone 16 x 6 x 5 for cor. to secs. 13 and 24 on E. slope of hill. Land; sand hilly and broken.
	S. 14' W. on a true line along the E. Bdy. of Sec. 24