

## E. Bdy. T. 3 S. R. 29. E.

Chains		Feet
	Var. 19° 25' E.	
5.00	Top of hill sloping W.	
40.00	Set stone 32 x 12 x 8 for $\frac{1}{4}$ Sec. Cor. on S. side of hill.	
44.00	Bottom of gulch.	
58.50	Top of low R. sloping W.	
68.80	Bottom of gulch.	
80.00	Set stone 18 x 8 x 6 for cor. to Secs. 24 and 25 on top of steep hill.	
	Land; very hilly and broken.	
	S. 14' W. on a true line along the E. Bdy. of Sec. 25.	
	Var. 21° 45' E.	
16.00	Top of flat hill.	
34.00	From this point Robinsons Sheep Corall brs. S. 54° E about 100 chs. dist.	
40.00	Set stone 18 x 9 x 4 for $\frac{1}{4}$ Sec. cor.	
65.00	Top of low hill.	
79.00	Cross bottom of gulch.	
80.00	Set stone 26 x 6 x 4 for cor. to Secs. 25 and 36 in shallow gulch 50 Lks. S. of water drain in gulch.	
	Land; hilly and broken.	
	S. 14' W. on a true line along the E. Bdy. of Sec. 36.	
	Var. 21° 45' E.	
40.00	Set stone 13 x 7 x 6 for $\frac{1}{4}$ Sec. cor. on N. E. slope of hill.	
73.00	Top of high hill.	
80.00	The cor. to T. 3 and 4 S. Rs. 29 and 30 E.	
	Land; very hilly and broken. Good grazing land only.	
	Sept. 20, 1872.	