

S. Bdy. T. 3 S., R. 30 E., W. M.

Chains		Feet
40.00	Set stone 20 x 14 x 10 on W. hillside for $\frac{1}{4}$ Sec. Cor.	+200
80.00	Set stone 22 x 18 x 8 on E. side near bottom of ravine for Cor. to Secs. 12 and 13, from which, A Balm, 12 ins. in diam., brs. S. 43° W., 16 lks. dist. A Balm, 11 ins. in diam., brs N. 85° W. 43 lks. dist. No other trees convenient to mark. Land; surface high, rolling hills, Soil 2nd and 3rd and 1st rate. Some good agricultural land, mostly only good for grazing. Good grass. Balm, Willow and Alder along creek. October 28th 1878	
	S. along the E. Bdy. of Sec. 13. Var. 24° 15' E.	
1.00	Brook 6 lks. wide course N.W. Begins ascent of mountains.	
40.00	Set stone 14 x 10 x 5 on W. side of ridge for $\frac{1}{4}$ Sec. Cor.	+400
80.00	Set stone 24 x 14 x 16 on N. W. mountain side for Cor. to sections 13 & 24. Dug pits, drove stake, and raised mounds of stone around stone and stake. Land; surface, mountainous. Soil; 2nd and 3rd rate, good grass, well adapted to grazing	
	S. on the E. Bdy. of Sec. 24. Var. 20° E.	
24.00	Begin to descend S. W. side of ridge.	+150
40.00	Set stone 16 x 10 x 7 on S. W. side of ridge for $\frac{1}{4}$ Sec. Cor.	-150
45.50	Ravine course W.	-100
52.50	On rocky point extends W.	+150
76.00	Enter timber S. E. & N. W.	
80.00	Set stone 18 x 14 x 10 on E. side of ravine for Cor. to Secs. 24 and 25 from which, A Pine 30 ins. diam. brs. N. 78° E 80 lks dist.	