

S. Bdy. T. 3 S., R. 30 E. W.M.

Chains		Feet
	<p>W. on a random line along the S. Bdy. of Secs. 36, 35, 34, 33, 32 and 31.</p> <p style="text-align: right;">Var. 21° 45' E.</p> <p>I set temp. halfmile and mile posts at 40.00 and 80.00 Chs. and 6 miles 1 chain and 84 lks. to a point 186 lks. S. of corner to Tps. 3 and 4 S. Rs. 29 and 30 E. My correction will be 31 lks. N. per mile. I find the Cor. stone standing as described in the field notes furnished me by the surveyor's Generals Office.</p> <p>From the Cor. to Tps. 3 and 4 S. Rs. 29 and 30 E. I run, S. 89° 47' E. on a true line along the S. Bdy. of Sec. 31.</p>	
33.00	Road S. W. & N. E.	
41.84	Set stone 13 x 10 x 7 in low flat for $\frac{1}{4}$ Sec. Cor.	-300
57.00	On ridge	+200
74.00	In ravine course. N. & S.	-200
81.84	Set stone 18 x 10 x 8 on W. side of ridge for corner to Sec. 31, 32, 5 and 6.	
	Dug pits and drove stake and raised mounds of stone around stone and stake.	
	Land; surface broken,	
	Soil; 3rd and 2nd rate; good grass,	
	Groves of pine on S. of line.	
	S. 89° 47' E. along the S. Bdy of Sec 32.	
	Var. 21° E.	
12.00	On ridge course N. and S.	+100
29.50	Brook 10 lks. wide course N.	-150
30.50	Road course N. and S. to timber	
40.00	Set stone 16 x 8 x 5 on west side of ridge for $\frac{1}{4}$ Sec. Cor.	+100
	There are several farms in the valley about $1\frac{1}{2}$ miles N.	
52.00	On ridge extends N. and S.	+100
67.00	Ravine opens N.	-100
80.00	Set stone 14 x 12 x 7 on N. W. slope of ridge for corner to Sections 32, 33, 4 and 5.	
	Dug pits, drove stake and raised mounds of stone around	