

## Subdivisional Lines, T. 3 S., R. 30, E.

Chains		Feet
	Var. 21° 15' E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.64	Intersected E. Bdy. 22 lks. N. of Cor. to Sec. 12 & 13 from which Cor. I run,	
	N. 89° 51' W. on a true line between Sec. 12 & 13,	
	Var. 24° 30' E.	
40.32	Set Basalt stone 16 x 8 x 5 at E edge of creek bottom for $\frac{1}{4}$ Sec. Cor. A Pine 10 in. diam. brs. N. 48 lks. dist. A Birch 18 in. diam. brs. S 24° W. 75 lks. dist.	
43.00	Butter. Creek 20 lks. wide, course. N.	
45.00	Bluff, leave bottom	
80.64	The Cor. to Sec. 11, 12, 13 & 14 Land; surface very broken, Soil; 3rd rate on creek bottom 1st rate, some Pine and Balm timber on creek, also underbrush, good grass.	+300
	N. between Sec. 11 & 12	
	Var. 21° 15' E	
39.50	In gulch, course N. W.	-250
40.00	Set Basalt stone 16 x 12 x 8 on N. side of gulch for $\frac{1}{4}$ Sec. Cor	
79.00	Gulch opens N. E.	-100
80.00	Set Basalt stone 14 x 10 x 5 and marked stake in mounds of stone on E. side of rocky spur for course to Secs. 1, 2, 11 & 12. Land; surface, very broken, Soil 3rd and 2nd rate, good grass, adapted to grazing.	
	E. on random line between Secs. 1 & 12,	
	Var. 23° 45' E.	
40.00	Set post for temporary $\frac{1}{4}$ Sec. Cor.	
80.56	Intersected E. Bdy. 46 lks. N. of Cor. to Sec. 1 & 12 from which Cor. I run, N. 89° 40' W. on a true line between Sec. 1 & 12 Var. 20° 00' E.	