

Subdivisional Lines, T. 3 S., R. 30 E.

Chains		Feet
52.00	Fence, course E and W and field Joel W. Thrashers' house brs. S. 30° E.	
79.00	Fence, N. W and S. E., leave field,	
80.00	Set quartz stone 16 x 10 x 5 on level in mound of stone and drove post for Cor. to Sec. 28, 29, 32 and 33. Land; surface N. 65 Chs, undulating, Soil; 1st and 2nd rate, good grass, good farming land.	
<hr/> E. on a random line between Sec. 28 and 33, Var. 21° 15' E.		
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.02	Intersected N. & S. line 28 lks. N of Cor. to secs. 27, 28, 33, & 34. from which Cor. I run, N. 89° 48' W. on a true line beyween Sec. 28 & 33. Var. 20° 45' E.	
40.01	Set Basalt stone 18' x 12 x 4 on low ridge for $\frac{1}{4}$ Sec. Cor.	
74.00	Road to timber	
80.02	The Cor. to Sec. 28, 29, 32 & 33 Land; surface rolling, Soil; 2nd 1st & 3rd rate, good grass, well adapted to farming. Sept. 13, 1879	- 80
<hr/> N. between Sec. 28 & 29, Var. 21° 15' E		
4.50	Wagon road N. W. & S. E.	
40.00	Set Basalt stone 14 x 10 x 5 on W. hillside for $\frac{1}{4}$ Sec. Cor.	
44.00	Road N.E. & S.W.	
47.50	Brook 4 lks. wide, course N.W.	
80.00	Set Basalt stone 17 x 12 x 3 and post in mound of stone on E. hillside for Cor. to Secs. 20, 21, 28 & 29. Land; surface rolling, Soil; 3rd and 2nd rate, good grass. Some good farming land.	- 50