

Subdivisional Lines, T. 3 S., R. 30 E.

Chains		Feet
38.80	Set Basalt stone 17 x 12 x 5 in shallow ravine for $\frac{1}{4}$ Sec. Cor.	- 30
78.80	The Cor. to Sec. 4, 5, 8 & 9, Land; surface rolling, Soil; 2nd rate, some 3rd rate, good grass. Large part good for farming.	+140
<hr/>		
	N. between Sec. 31 & 32. Var. 18° 45' E. Down along E. side of and across to W. side of Spur.	
40.00	Set Basalt stone 16 x 8 x 5 on W. side of spur for $\frac{1}{4}$ Sec. Cor.	
43.00	Foot of mountains proper, cluster of springs.	-150
49.50	Fence and field, course N. W. & S.E.	
56.50	Fence, leave field, N.E. & S.W.	
74.00	Brook 12 lks. wide, course N.W. & road course N. & S.W.	
78.50	Road course S.E. & N.W. to timber	
80.00	Set Basalt stone 17 x 10 x 4 and post in mound of stone on S.W. face of hill for Cor. to Secs. 29, 30, 31, & 32. Land; surface on S. $\frac{1}{2}$ mile mountainous, N. $\frac{1}{2}$ mile undulating, Soil; S. $\frac{1}{2}$ mile 3rd rate N. $\frac{1}{2}$ mile 1st and 2nd rate and excellent farming land.	
<hr/>		
	E. on a random line between Sec. 29 & 32, Var. 21° 00' E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.08	Intersected N. & S. line at Cor to Sec. 28, 29, 32 & 33., from which Cor. I run, Var. 21° 45' E	
	W. on a true line between Secs. 29 & 30.	
.50	Fence & field, course n.W. & S.E.	
4.00	Wm. H. Simon's house 15 lks. N.	
16.00	Fence, course N. & S., leave field	
40.04	Set white quartz stone 17 x 10 x 4 on S.E. slope for	