

Subdivisional Lines, T. 3 S., R. 30 E.

| Chains | | Feet |
|--------|--|------|
| | E. on a random line between Sec. 20 & 29. Var. 19° 45' E | |
| 40.00 | Set post for temp. $\frac{1}{4}$ Sec. Cor. | |
| 79.82 | Intersected N. & S. line 48 lks, N. of Cor. to Secs. 20, 21, 28 & 29 from which Cor. I run, N. 89° 39' W. on a true line between Sec. 20 & 29, Var. 22° 30' E. | |
| 39.91 | Set Basalt stone 24 x 14 x 6 on W. slope for $\frac{1}{4}$ Sec. Cor. | |
| 74.00 | Wagon road, course N.E. & S.W. to timber | |
| 79.82 | The Cor. to Secs. 19, 20, 29 & 30. Land; surface rolling, Soil; 3rd and 2nd rate, good grass, nearly all of Sec. 29 is good farming land, Sept. 15, 1879 | - 50 |
| | W. on a random line between Sec. 19 & 30, Var. 19° 45' E. | |
| 40.00 | Set post for temp. $\frac{1}{4}$ Sec. Cor. | |
| 82.30 | Intersected W. Bdy. 70 lks. S. of Cor. to Sec. 19 & 30 from which Cor. I run, S. 89° 30' E. on a true line between Sec. 19 & 30. Var. 21° 45' E. | |
| 14.00 | Brook 8 lks. wide, course n.W. | - 80 |
| 42.30 | Set Basalt stone 20 x 12 x 8 on S. E. face of hill for $\frac{1}{4}$ Sec. Cor | +100 |
| 82.30 | The Cor. to Sec. 19, 20, 29 & 30. Land; surface rolling, Soil; 3rd and 2nd rate, small part 1st rate, along brook. Good grass, some good farming land in Sec. 30. | |
| | N. between Sec. 19 & 20, Var. 19° 45' E | |
| 40.00 | Set Basalt stone 14 x 12 x 4 on E. hillside for $\frac{1}{4}$ Sec. Cor. | |
| 80.00 | Set Basalt stone 20 x 12 x 8 and post in mound of stone | |