

Subdivisional Lines, T.3 S., R.30 $\frac{1}{2}$ E., W. M.

Chains		Feet
	Var. 14°15'E.	
8.00	Gulch opens N.E.	-150
11.26	Cor. to Secs. 25, 26, 35 & 36.	- 40
	Land; surface steep hillside.	
	Soil; 3rd rate, good grass.	
	<hr/>	
	N. bet. Secs. 25 & 26.	
	Var. 20°45'E.	
6.50	Gulch opens N.E. & leave timber	- 50
40.00	Set basalt stone, 17 x 12 x 4 on E. hillside for $\frac{1}{4}$ Sec. Cor.	- 50
	A pine, 12 ins. diam., brs. S.33°E., 122 lks. dist.	
	No tree on W. side.	
42.00	Enter timber, course S.E. & N.W.	
46.00	Leave gulch, opens N.W. also	-120
80.00	Set basalt stone, 16 x 8 x 6 and post in mound of stone on	200
	W. side of ridge, for Cor. to Secs. 23, 24, 25 & 26.	
	Land; surface mountainous.	
	Soil; 3rd rate. Good grass.	
	Some good timber, pine & fir.	
	<hr/>	
	E. on random line bet. Secs. 24 & 25.	
	Var. 19°15'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.74	Intersected E. Bdy., 118 lks. S. of Cor. to Secs. 24, & 25,	
	from which Cor., I run	
	S.89°09' W. on true line bet. Secs. 24 & 25.	
	Var. 21°15'E.	
40.37	Set basalt stone, 16 x 10 x 8 on N.W. slope, for $\frac{1}{4}$ Sec. Cor.	
80.74	The Cor. to Secs. 23, 24, 25 & 26.	-700
	Land; surface mountainous.	
	Soil; 3rd rate & 2nd rate. Good grass.	
	About 1/3 of Secs. 25 is covered with good timber in the	
	S.E. part, pine, tamarack & fir.	
	<hr/>	
	W. on random line bet. Secs. 23 & 26.	
	Var. 19°15'E.	