

Subdivisional Lines, T.3 S., R.30 $\frac{1}{2}$ E., W. M.

Chains		Feet
11.28	Intersected W. Bdy., 20 lks. N. of Cor. to Secs. 23 & 26, from which Cor., I run N.89°00'E. on true line bet. Secs. 23 & 26. Var.22°45'E.	
11.28	The Cor. to Secs. 23, 24, 25 & 26. Land; surface steep hillside. Soil; 3rd rate. Good grass. Sept. 3, 1879.	+250
	N. bet. Secs. 23 & 24. Var.19°15'E.	
34.00	Gulch opens N.W.	
40.00	Set basalt stone, 18 x 8 x 5, on S.W. face of hill, for $\frac{1}{4}$ Sec. Cor.	
60.00	Leave mountains proper.	-250
80.00	Set basalt stone, 18 x 12 x 4 on E. slope of ridge and post in mound of stone for Cor. to Secs. 13, 14, 23 & 24. Land; surface mountainous. Soil; 3rd & 2nd rate. Good grass. Good for grazing.	
	E. on random line bet. Secs. 13 & 24. Var.19°15'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.68	Intersected E. Bdy., 142 lks. S. of Cor. to Secs. 13 & 24, from which Cor., I run S.88°59' W. on true line bet. Secs. 13 & 24. Var.21°00'E.	
40.34	Set basalt stone, 18 x 12 x 5 on knoll, for $\frac{1}{4}$ Sec. Cor.	
63.50	Brook, 10 lks. wide, course N.W.	-200
80.68	The Cor. to Secs. 13, 14, 23 & 24. Land; surface some broken. Soil; 3rd rate, small part on brook 1st rate, good for farm- ing. Some pine & balm timber on brook.	+200