

## Subdivisional Lines, T.3 S., R.30½ E., W. M.

Chains		Feet
	W. on random line bet. Secs. 14 & 23. Var. 19°15'E.	
11.28	Intersected W. Bdy., 18 lks. N. of Cor. to Secs. 14 & 23, from which Cor., I run N.89°04'E. on true line bet. Secs. 14 & 23. Var. 20°00'E.	
11.28	The Cor. to Secs. 13, 14, 23 & 24. Land; surface rolling. Soil; 3rd rate. Good grass.	
	N. bet. Secs. 13 & 14. Var. 19°15'E.	
	Along E. slope of ridge.	
40.00	Set basalt stone, 12 x 10 x 8, on N. descent of ridge, for ¼ Sec. Cor.	
69.50	A brook, 8 lks. wide, course N.W.	200
80.00	Set basalt stone, 20 x 8 x 5 on S.W. face of hill, for Cor. to Secs. 11, 12, 13 & 14, also set post in mound of stone. Land; surface some broken. Soil; 3rd & 2nd rate. Good grass. Alder & willow brush along brook.	100
	E. on random line bet. Secs. 12 & 13. Var. 21°30'E.	
40.00	Set post for temp. ¼ Sec. Cor.	
80.52	Intersected E. Bdy., 122 lks. S. of stone Cor. to Secs. 12 and 13, from which Cor., I run S.89°08' W. on true line bet. Secs. 12 & 13. Var. 20°00'E.	
	House brs. N.37°W.	
	" " " N.24°W.	
15.00	1st " " N.20°W.	
	2nd " " N.10°E.	
40.26	Set basalt stone, 18 x 10 x 7 on N. slope for ¼ Sec. Cor.	
80.52	The Cor. to Secs. 11, 12, 13 & 14.	50