

## Exterior Lines, T.3 S., R.31 E., W. M.

| Chains |  | Feet            |
|--------|--|-----------------|
| 40.00  | Set stone, 16 x 8 x 6 in mound of stone for $\frac{1}{4}$ Sec. Cor.  | + 80            |
| 45.00  | Begin to ascend mountains.   |                 |
| 63.00  | Summit of ridge, S.E. & N.W.   | +300            |
| 80.00  | Set stone, 17 x 12 x 5 on S. side of ridge, in mound of stone, for Cor. to Secs. 18, 19, 13 & 24; dug pits & drove stake, as per instructions. | -200            |
|        | Land; surface, N. $\frac{1}{2}$ mile rolling- S. $\frac{1}{2}$ mile mountainous.   |                 |
|        | Soil; 2nd & 3rd rate, good grass. N. $\frac{1}{2}$ mile good for farming.  |                 |
|        | S. along W. Bdy. of Sec. 19.   |                 |
|        |  | Var. 21° E.     |
| 4.50   | Enter timber, E. & W.  | -150            |
| 5.50   | Brook, 10 lks. wide, course W.   |                 |
| 11.00  | Leave timber, course E. & W.   |                 |
| 40.00  | Set stone, 15 x 12 x 4 on N.E. hillside for $\frac{1}{4}$ Sec. Cor.  | +350            |
| 80.00  | Set stone, 14 x 10 x 5 on E. hillside, in point of timber, for Cor. to Secs. 19, 30, 24 & 25, from which,                                      |                 |
|        | A pine, 10 ins. diam., brs. S. 70° E., 60 lks. dist.,  |                 |
|        | A pine, 13 ins. diam., brs. N. 10° W., 138 lks. dist.  |                 |
|        | A pine, 24 ins. diam., brs. N. 68° E., 172 lks. dist.  |                 |
|        | No other trees.  |                 |
|        | Land; surface, mountainous.  |                 |
|        | Soil; 2nd & 3rd rate.  |                 |
|        | Some pine timber in gulches. Good grass.   |                 |
|        | S. on W. Bdy. of Sec. 30.  |                 |
|        |  | Var. 21° 15' E. |
| 40.00  | Set pine post, in grove of timber, for $\frac{1}{4}$ Sec. Cor.   |                 |
|        | A pine, 10 ins. diam., brs. N. 22° E., 27 lks. dist.   |                 |
|        | A pine, 17 ins. diam., brs. N. 50° W., 45 lks. dist.   |                 |
| 47.00  | Enter main timber, E. & W.   |                 |
| 49.00  | Spring branch, course N.W.   | -150            |
| 67.00  | Leave timber, S.E. & N.W.  | +150            |
| 80.00  | Set stone, 14 x 10 x 4, in mound of stone, in open level, for Cor. to Secs. 30, 31, 25 & 36.   |                 |
|        | Could not dig pits; raised mound of stone around stake in  |                 |