

Subdivisional Lines, T.3 S., R.31 E., W. M.

Chains		Feet
	Var. 20° E.	
25.00	Brook, 8 lks. wide, course N.	300
39.98	A fir, 14 ins. diam. for $\frac{1}{4}$ Sec. Cor.	300
	A fir, 18 ins. diam., brs. N. 58° E., 31 lks. dist.	
	A pine, 22 ins. diam., brs. S. 22° E., 46 lks. dist.	
60.50	Road to Camas Prairie, course N. & S.	
63.00	Enter small prairie, course N. & S.	
79.96	Cor. to Secs. 13, 14, 23 & 24.	
	Land; surface mountainous.	
	Soil; 3rd rate.	
	Heavy timber E. of prairie, some small open glades, pine fir & tamarack, some young timber underbrush.	
	N. bet. Secs. 13 & 14.	
	Along W. mountain side.	Var. 25° 30' E.
33.00	Enter timber, E. & W.	
40.00	Set basalt stone. 16 x 12 x 10 on N.W. point of spur, for $\frac{1}{4}$ Sec. Cor.	150
	A pine, 15 ins. diam., brs. S. 117 lks. dist.	
	A pine, 20 ins. diam., brs. N. 70° W., 78 lks. dist.	
	Down irregular W. mountain side.	
80.00	Set basalt stone, 14 x 10 x 5 on W. mountainside, for Cor. to Secs. 11, 12, 13 & 14.	300
	A pine, 10 ins. diam., brs. N. 38° E., 52 lks. dist.	
	A pine, 24 ins. diam., brs. S. 70° E., 38 lks. dist.	
	A pine, 13 ins. diam., brs. S. 28° W., 89 lks. dist.	
	A pine, 16 ins. diam., brs. N. 22° W., 138 lks. dist.	
	Land; surface mountainous.	
	Soil; 3rd rate.	
	Good timber on N. part, pine, tamarack & fir. Good grass on prairie.	
	E. on random line bet. Secs. 12 & 13.	
		Var. 21° 45' E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.86	Intersected E. Bdy., 30 lks. S. of stone Cor. to Secs. 12	