

## Subdivisional Lines, T.3 S., R.31 E., W. M.

Chains		Feet
	N. bet. Secs. 14 & 15. Var. 21°15'E.	
9.50	Spring branch, course N.E.	
40.00	Set granite stone, 16 x 12 x 8 on N.E. slope for $\frac{1}{4}$ Sec. Cor. A fir, 15 ins. diam., brs. S.38°E., 25 lks. dist. A pine, 10 ins. diam., brs. N.14°W., 73 lks. dist.	
78.50	Sawmill of Wm. H. Beasley, Jun.	
80.00	Set granite stone, 18 x 16 x 10 on E. bank of brook, just below sawmill, for Cor. to Secs. 10, 11, 14 & 15, A fir, 12 ins. diam., brs. N.22°E., 70 lks. dist. A fir, 24 ins. diam., brs. N.30°W., 12 lks. dist. No other trees. Land; surface mountainous. Soil; 3rd rate. Heavy timber; pine, tamarack & fir. Some young timber underbrush.	- 60
	E. on random line bet. Secs. 11 & 14. Var. 21°E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.76	Intersected N. & S. line, 82 lks. S. of stone Cor. to Secs. 11, 12, 13 & 14, from which Cor., I run S.89°25'W., on true line bet. Secs. 11 & 14. Var. 21°45'E.	
35.00	Spring branch, course S.W.	
40.38	Set granite stone, 16 x 10 x 8 on N. side of ravine, for $\frac{1}{4}$ Sec. Cor. A pine, 14 ins. diam., brs. N.50°W., 131 lks. dist. A pine, 42 ins. diam., brs. S.62°W., 58 lks. dist.	
64.00	William H. Beasley's, Jun.- house, brs. N. 2 chs.	
80.76	The Cor. to Secs. 10, 11, 14 & 15. Land; surface mountainous. Soil; 1st & 3rd rates, much is good for farming. Timber; nearly all cut away, pine & tamarack. Willis B. Beasley's house is on N.W. $\frac{1}{4}$ of Sec. 14, near sawmill.	-500