

Subdivisional Lines, T.3 S., R.31 E., W. M.

Chains		Feet
	N. bet. Secs. 10 & 11. Var. 21°E,	
5.50	Leave timber & road, N.W. & S.E.	
6.50	Fence, N.W. & S.E.	
40.00	Set stone, basalt, 18 x 12 x 5, on N. side of ravine, opening westward, for $\frac{1}{4}$ Sec. Cor. A pine, 42 ins. diam., brs. S. 28°E., 104 lks. dist. No other tree near.	
71.00	Road to sawmill, N.W. & S.E., through farm.	
73.00	Fence, course E. & W., on N. side of Wm. Beasley's farm.	
80.00	Set basalt stone, 18 x 12 x 5 on S. side, near top of Mt. for Cor. to Secs. 2, 3, 10 & 11; set stake & raised mounds of stone around stone & stake, in lieu of pits. Land; surface mountainous. Soil; 1st & 2nd rates, good grass, good for farming. Most of Secs. 11 is good farming land. May 5, 1879.	500
	E. on random line bet. Secs. 2 & 11. Var. 23°15'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.76	Intersected N. & S. line, 88 lks. S. of Cor. to Secs. 1, 2, 11 & 12, from which Cor., I run S. 89°22'W. on true line bet. Secs. 2 & 11. Var. 24°15'E.	
33.00	Spring branch, course N.	
40.38	Set basalt stone, 14 x 12 x 8 on E. slope, for $\frac{1}{4}$ Sec. Cor.	
80.76	Tha Cor. to Secs. 2, 3, 10 & 11. Land; surface mountainous. Soil; 3rd & 2nd rates and stony. Good bunch grass.	100
	N. on random line bet. Secs. 2 & 3. Var. 23°15'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.52	Intersected N. Bdy., 137 lks. E. of post in mound Cor. to	