

Exterior Lines, Tp. 4, S., R. 32 E. W. M.
 As surveyed by George S. Pershin, U. S. Deputy Surveyor
 Under contract No. 390,
 Dated May 12, 1881.

Chains		Feet
	W. on the N. Bdy. of Sec. 1,	
	Var. 15° 30' E.	
40.00	Set basalt stone 16 x 12 x 4 on W. slope for $\frac{1}{4}$ Sec. Cor. A Pine 10 in. diam. brs., N. 30° E. 71 lks. dist. " " 16 " " " S. 18° W. 65 " "	
52.50	A brook 8 lks. wide, course S.	
80.00	Set basalt stone 17 x 12 x 8 on level for Cor. to Secs, 1, 2, 35 & 36. A Pine 32 in. diam brs. N. 42° E. 52 lks, dist. " " 26 " " " S 23° E. 54 lks dist. " " 26 " " " S. 38° W. 133 lks dist. " " 38 " " " N. 15° W. 66 " "	
	Land; surface undulating and rolling, Soil; 3rd and 2nd rate, Pine, Tamarack and Fir timber with open glades, good grass in openings; some dense thickets of young timber.	
	W. on the N. Bdy. of Sec. 2,	
	Var. 18° 45' E	
40.00	Set Basalt stone 14 x 10 x 5 on slight S.E. slope for $\frac{1}{4}$ Sec. Cor. A Pine 7 in. diam brs. N. 7° E. 54 lks, dist. " Tamarack 6 in. diam. brs. S. 17° E. 46 lks. dist.	
80.00	Set Pine post on level for Cor. to Secs. 2, 3, 34 & 35. A Pine 4 in. diam. brs. N. 28° E. 30 lks. dist. " " " " " S. 54° E. 12 lks. dist.	
	No tree S.W. A Tamarack 4 in. diam. Brs. N. 60° W. 20 lks dist.	
	Land; surface undulating, Soil; 2nd and 3rd rate, mostly a dense growth of young Pine, Tamarack and Fir timber with a few small open- ings.	
	W. on the N. Bdy. of Sec. 3,	
	Var. 20° 00' E.	