

## Exteriors Bdy. Lines of T. 3 S., R. 32 E.

Chains	Feet
<p>A Fir 5 ins. diam brs. S. 53° E. 38 lks. dist.  Marked T. 3 S., R. 33 E. S. 6 B.T.</p> <p>Land; surface mountainous.</p> <p>Soil; 3rd rate, heavily timbered with Pine, Tamarack and  Fir, with some open glades.</p> <p style="text-align: right;">May 27, 1882.</p>	
<hr/> <p>After having subdivided nearly all this township and failed to find the Cors. on N. Bdy. I find the Cor. to Sec. 31 and 32 which is a stone about 18 x 12 x 7 on S. slope in mound of stone. I begin at this Cor. and re-run this N. Bdy.</p> <p>Note: for record of this retracement see T. 2 S., R. 32. E.</p>	
<hr/> <p>Subdivisional Bdy Lines of Tp. 3 S., R. 32 E. W.M.  As surveyed by George S Pershin, U.S. Deputy Surveyor.  Under Contract No. 430.  Dated March 23, 1882.</p>	
<hr/> <p>Having surveyed the E. Bdy of this Tp. myself with my present assistants I do not retrace the E. and S. Bdys. of Sec. 36.</p> <p>I begin at the Cor. to Sec. 35 and 36 on the S. Bdy of this Tp. which is a stone projecting 7 inches above ground and marked with one notch on E. and 5 notches on W. edges from which,</p> <p>A Pine 32 ins. diam. brs. N. 42° E. 52 lks. dist.  Marked T. 3 S., R. 32 E. S. 36 B.T.</p> <p>A Pine 26 ins. diam. brs. S. 23° E. 54 lks. dist.  Marked T. 4 S., R. 32 E. S. 1 B.T.</p> <p>A Pine 26 ins. diam brs. S. 38° W 133 lks. dist.  Marked T. 4 S., R. 32 E. S. 2 B.T.</p> <p>A Pine 38 ins. diam. brs. N. 15° W. 66 lks. dist.  Marked T. 3 S., R. 32 E. S. 35 B.T.</p>	
<hr/> <p>Survey commenced May 16, 1882.</p> <p>N. bet. Sec. 35 &amp; 36,</p>	