

Subdivisional Lines of T. 3 S., R. 32 E.

Chains		Feet
	<p>Marked $\frac{1}{4}$ S. B.T.</p> <p>A Pine 36 ins. diam. brs. S. 76° E. 47 lks. dist.</p> <p>Marked $\frac{1}{4}$ S. B.T.</p>	
80.04	<p>The Cor. to Secs. 4, 5, 8 and 9</p> <p>Land; surface mountainous and broken.</p> <p>Soil; 3rd and 2nd rate, Pine, Tamarack and Fir timber with dense underbrush $\frac{3}{4}$ of the distance Willow. Thorn, Rosebush, Young Fir and some open glades.</p>	
	<hr/> <p>W. bet. Secs. 5 and 8,</p> <p style="text-align: right;">Var. $21^{\circ} 15' E$</p> <p>Rapidly ascending</p>	
38.00	<p>Top of ridge, course N. and S.</p> <p>Ascent about 350 ft.</p>	
40.00	<p>Set a basalt stone 18 x 10 x 6, 12 ins. in ground on slight N. slope for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. No trees raised, Raised a mound of stone along side in lieu of pits.</p>	
55.85	<p>Intersected W. Bdy 12.35 chs. N. of Cor. to Secs. 1 and 12 of T. 3 S., R. 31 E.</p> <p>Set a basalt stone 12 x 8 x 6 ins. and a post three ft. long 5 ins. diam. faced on N. E. & S.E., in mound of stone on slight N. slope for Cor. to Secs. 5 and 8, stone marked with 5 notches on S. and E. edges, and post marked with T. 3 S., S. 5 on N.E. and R. 32 E., S E. face. No trees.</p> <p>Land; surface mountainous,</p> <p>Soil; 2nd rate, some Pine, Tamarack and Fir timber on E. $\frac{1}{2}$ mile, W. $\frac{1}{2}$ mile open. Good grass.</p> <p>Note:- Thom. J. Purrdys' improvement is on Sec. 8, but cannot be seen from line.</p>	
	<hr/> <p>N. bet. Secs. 4 and 5,</p> <p style="text-align: right;">Var. $21^{\circ} 15' E$.</p>	
28.00	<p>E. H. Olcott's house brs. E. about 16 chs.</p>	