

Subdivisional Lines, T.3 S., R.33 E., W. M.

Chains	Feet
80.00	<p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 27, 28, 33 & 34, marked</p> <p>T.3 S., S.27 on N.E. R.33 E., S.28 on N.W. S.33 on S.W. and S.34 on S.E., with 1 notch on S. and 3 on E. edges, from which</p> <p>A pine, 3½ ins. diam., brs. N.67°W., 10 lks. dist., marked R.33 E., S.28, B.T. A pine, 4 ins. diam., brs. S.34°W., 46 lks. dist., marked S.33, B.T. A pine, 4 ins. diam., brs. S.21°E., 22 lks. dist., marked S.34, B.T. A pine, 5 ins. diam., brs. N.54°E., 21 lks. dist., marked S.27, B.T.</p>
	<p>Land; rolling hills. Soil; 2nd rate. Heavily timbered with pine & fir. Dense undergrowth of pine & fir.</p>
	<p>E. on random line bet. Secs. 27 & 34. Var. 20°30'E.</p>
20.25	20.25 Brook, 3 lks. wide, runs S.E.
40.00	Set temp. ¼ Sec. Cor. Descend.
66.00	Creek, 6 lks. wide, runs N.E. 400 ft. below ¼ Sec. Cor. Ascend.
80.00	Intersect N. & S. line, 49 lks. N. of Cor. to Secs. 26, 27, 34 & 35.
	<p>Thence I run N.89°39'W. on true line bet. Secs. 27 & 34.</p>
40.00	<p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for ¼ Sec. Cor., marked ¼ S. on N. face, from which,</p> <p>A pine, 5 ins. diam., brs. S.69°E., 73 lks. dist., marked ¼ S., B.T. A pine, 6 ins. diam., brs. N.63°W., 78 lks. dist.,</p>