

Subdivisional Lines, T.3 S., R.33 E., W. M.

Chains	Heavily timbered with pine, fir & tamarack. Dense undergrowth of pine & fir.
	N. bet. Secs. 29 & 30. Gradually descend. Var. 21°E.
38.00	Ravine, course N.20°W., 200 ft. below Sec. Cor.
40.00	Set basalt stone, 16 x 10 x 5 ins., 12 ins. in ground, for ¼ Sec. Cor., marked ¼ on W. face, from which A fir, 7 ins. diam., brs. S.78°W., 12 lks. dist., marked ¼ S., B.T. A fir, 12 ins. diam., brs. S.70°E., 42 lks. dist., marked ¼ S., B.T.
60.00	Steep descent.
79.50	Enter creek bottom, brs. N.80°E.
80.00	Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 19, 20, 29 & 30, marked T.3 S., S.20 on N.E. R.33 E., S.19 on N.W. S.30 on S.W. and S.29 on S.E., with 2 notches on S. and 5 on E. edges, from which, A pine, 6 ins. diam., brs. N.35°W., 38 lks. dist., marked R.33 E., S.19, B.T. A pine, 4 ins. diam., brs. N.42°E., 24 lks. dist., marked T.3 S., S.20, B.T. A pine, 4 ins. diam., brs. S.76°E., 62 lks. dist., marked S.29, B.T. A pine, 6 ins. diam., brs. S.15°W., 34 lks. dist., marked S.30, B.T.
	500 ft. below ¼ Sec. Cor.
	Land; mountainous.
	Soil; 2nd rate.
	Heavily timbered with pine, fir & tamarack.
	Dense undergrowth of pine & fir.