

Exterior Bdys. of T. 4 N., R. 28 E., W.M.
 As surveyd by Ebenezer E. Haft, U.S. Deputy Surveyors.
 Under Contract No. 93,
 Dated Sept. 11, 1860.

Chains	Feet
	From the Cor., to Tps. 3 & 4 N. Rgs. 27 & 28 E., W.M. I run, N. bet. Secs. 31 and 36, September 28, 1860 Var. 20° E.
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench and pits, and deposited 1 pint of charcoal as per instructions.
80.00	Set post for Cor., to Secs. 25, 36, 31 & 30, in mound with trench and pits, and deposited 1 pint of charcoal as per instructions. Soil; sandy, sterile and destitute of vegetation.
	N. bet. Secs. 25 & 30 Var. 20° 3' E.
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal, as per instructions.
80.00	Set post for Cor., to Secs., 24, 25, 19 & 30, in mound with trench and pits, and deposited 1 pint of charcoal, as per instructions. Soil; sandy, 3rd rate, producing prickly pear and bunch grass.
	N. bet. Secs. 19 & 24 Var. 20° 10' E.
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits, and deposited 1 pint of charcoal, as per instructions.
80.00	Set post for Cor., to Secs., 18, 19, 13 & 24, in mound with trench and pits and deposited 1 pint of charcoal as per instructions. Soil; sandy, 3rd rate. Prickly pear and bunch grass. Land; level
	N. bet. Secs. 13 & 18 Var. 20° 10' E.
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal, as per instructions.