

1st Standard Parallel N., R. 27 E., W.M.

Chains		Feet
	pits as per instructions.	
80.00	Set post for Cor. to Secs., 35 & 36, in mound of earth, trench and pits as per instructions.	
	Soil; sand and gravel, gently rolling, grass tolerably good, little sage, greasewood, cactus, rosin weed and wild bean.	
<hr/>		
	W. on S. Bdy. of Sec. 35	
	Var. 18° E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in drifting sand, no mound.	
80.00	Set post for Cor. to Secs., 34 & 35, pits, no mound, drifting sand.	
	Soil; sand, worthless, poor grass and scattering greasewood. Lead	
	Land; rolling.	
<hr/>		
	W. on S. Bdy. of Sec. 34	
	Var. 18° E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., pits, no mound, sand shifting.	
80.00	Set post for Cor. to Secs., 33 & 34, pits, no mound, shifting sand, rolling.	
	Soil; light and sandy, poor grass.	
	Little greasewood.	
<hr/>		
	Resurvey of S. Bdy. of T. 5 N., R. 27 E., W.M. As surveyed by, Nicholas O. Walden, U.S. Deputy Surveyor Under Contract No. 209, Dated July 6, 1874.	
<hr/>		
	To reestablish Standard Cor. on the S. Bdy. of Sec. 36, T. 5 N., R. 27 E., the old cors. being obliterated I began at the Standard Cor. to T. 5 N., R. 27 & 28 E., and run	
	W. on S. Bdy. of Sec. 36	
40.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	Drove charred stake, and raised mound of earth, with pits, etc., as per instructions, for Standard Cor. to Secs.	