

Remeasurements of N. Bdy. of T. 4 N., R. 28 E., W.M.

Chains		Feet
	Oct. 18, 1860	
	Beginning at the Closing Cor. for Tps. 4 N., R. 28 & 29 E., W.M.	
	W. on N. Bdy. of Sec. 1	
	Var. 20° E.	
26.20	Stand. $\frac{1}{4}$ Sec. Cor. for Sec. 36	
40.00	Set post for Closing $\frac{1}{4}$ Sec. Cor. in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	
66.20	Stand. Cor. for Secs. 35 & 36	
80.00	Set post for Closing Cor. to Secs. 1 & 2, in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	
	Soil; Sandy 3rd rate.	
	Land; rolling,	
	Sage wood.	
	<hr/>	
	W. on N. Bdy. of Sec. 2	
	Var. 20° E.	
26.20	Stand. $\frac{1}{4}$ Sec. Cor., for Sec. 35	
40.00	Set post for C. $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint	
66.20	Stand. Cor. for Sec. 34 and 35	
80.00	Set post for C. Cor. to Secs. 2 and 3, in mound with trench and pits and deposited 1 pint of charcoal, as per instructions.	
	Soil; 3rd rate.	
	Some high and rolling	
	<hr/>	
	W. on the N. Bdy. of Sec. 3	
	Var. 19° 55' E.	
26.20	Stand. $\frac{1}{4}$ Sec. Cor. for Sec. 34	
40.00	Set post for C. $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint of charcoal, as per instructions	
66.20	Standard Cor. for Sec. 34 & 33	
80.00	Set post for C. Cor., to Secs. 3 and 4, in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	