

Subdivisional Lines of T. 4 N., R. 28 E., W.M.

Chains		Feet
	per instructions.	
	Soil; 3rd rate. Land; gently rolling	
	On the S. part, a heavy growth of wild sage.	
		Oct. 19, 1860
		Oct. 20, 1860
	E. on random line bet. Secs. 1 and 12	Var. 19° 45' E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.80	Intersect N. and S. line, 70 lks. N. of the Cor. to Secs. 1, 12, 6 & 7, from which Cor. I run	
	N. 89° 30' W. on true line bet. Secs. 1 & 12	
40.40	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits, and deposited 1 pint of charcoal, as per instructions.	
80.80	The Cor. to Secs. 1, 2, 11 and 12.	
	Soil; 3rd rate. Land; rolling, covered with wild sage.	
	N. on a random line bet. Secs. 1 and 2	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
82.85	Intersect 1st Standard Parallel N., 95 lks. W. of the Closing Cor. to Secs. 1 & 2, from which Cor. I run	
	S. 0° 41' W. on true line bet. Secs. 1 and 2	
42.85	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits & deposited 1 pint of charcoal as per instructions.	
82.85	The Cor. to Secs. 1, 2, 11 and 12	
	Soil; sandy, 3rd rate. Land; rolling Undergrowth, thick growth of Sage.	
	N. bet. Secs. 34 & 35	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and drove charred stake, as per instructions.	
	S.E. Cor. of Mitchell Claim	
	Mitchell's house brs. N. 72° W.	
	Lanchess " " N. 49° E.	
53.20	Mitchells house brs. S. 74° W.	
	Lanches " " N. 68° E.	
	Neighborhood road up Umatilla, brs. E.	
78.00	Enter timber, and undergrowth	
80.00	Set post for Cor. to Secs. 26, 27, 34 & 35, from which	