

Subdivisional Lines of T. 4 N., R. 28 E., W.M.

Chains		Feet
69.00	Leave willow undergrowth on bank of Umatilla	
70.20	Enter thick undergrowth and timber.	
74.45	Spring, 30 lks. wide, rising about 1 ch. from the crossing	
75.75	Leave undergrowth and timber.	
80.25	The Cor. to Secs. 16, 17, 20 & 21	
	Soil; 3rd rate. Land; level with growth of sagewood	
<hr/>		
	N. bet. Secs. 16 & 17	
6.50	Enter willow on bank of Umatilla	
7.50	Umatilla river, 1.40 chs. wide, runs, E.NE....	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits, and deposited 1 pint of charcoal as per instructions.	
56.60	Intersect left bank of Umatilla, on a steep perpendicular bluff, 75 ft. high; from the opposite bank flag at in- tersection, brs. S., chained a base E. 171 lks., flag brs. S. $25\frac{1}{2}^{\circ}$ W., 359 lks. across.	
60.19	Right bank of Umatilla	
80.00	Set post for Cor. to Secs. 8, 9, 16 & 17, in mound with trench and pits and deposited 1 pint of charcoal as per instructions.	
	Soil; 1st and 3rd rate, stony on bank of Umatilla. Land; principally level.	
<hr/>		
*	E. on random line bet. Secs. 9 & 16	
		Var. 20° E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.40	Intersect N. and S. line, 85 lks. N. of the Cor. to Secs. 9, 10, 15 & 16, from which Cor. I run N. $89^{\circ} 04'$ W. on true line bet. Secs. 9 & 16	
40.20	Set post for $\frac{1}{4}$ Sec. Cor., in mound with trench and pits and deposited 1 pint charcoal as per instructions.	
80.40	The Cor. to Secs. 8, 9, 16 & 17	
	Soil; sandy, 3rd rate, producing grass and sagewood Land; level.	
<hr/>		
	N. bet. Secs. 8 & 9	
40.00	Set post for $\frac{1}{4}$ Sec. Cor. in mound with trench and pits and deposited 1 pint charcoal as per instructions.	
51.00	Umatilla River, 160 lks. wide, runs E.	
58.50	Ascend a steep bank, 30 ft. high.	