

T. 4 N., R. 28 E., W.M.

Chains		Feet
	N. 31° 48' W. 11.82 chs., M. C. on N. Bdy. of sec.	
	Section 15	
	Found rocks with scribe marks set to perpetuate all cors. of this sec.	
	The NE cor. of Sec. 15 being visible from SE cor. I ran due	
	N. on line along the E. Bdy. of the sec. from the SE cor.	
40.12	$\frac{1}{4}$ cor. bet. secs. 14 and 15 on line.	
60.12	Set trial 1/16 cor. on line.	
80.12	NE cor. sec. 15.	
	Trail 1/16 cor. being in its right position, I set 2 x 4 ins. stake mkd. 1/16 in this position.	
	The NW cor. of the sec. being visible from the NE cor. I ran on line	
	N. 89° 35' W. from the NE cor. along the N. Bdy. of the sec.	
20.00	Set trial 1/16 cor. on line.	
40.00	$\frac{1}{4}$ cor. bet. secs. 10 and 15 on line.	
80.00	NW cor. of sec. 15.	
	Trail 1/16 cor. being in right position, I set 2 x 4 ins. post mkd. 1/16 in this position.	
	The SW cor. of sec. 15 and the SE cor. being intervisible from point on line between, I set hub at this point and ran	
	N. 89° 30' W. from the SE cor. along S. Bdy. of sec.	
39.77	$\frac{1}{4}$ cor. bet. Secs. 15 and 22 on line.	
54.45	Set 2 x 2 ins. stake on line mkd. W C.	
56.42	Meander cor. center O. R. & N. track.	
58.39	Set 2 x 2 ins. stake on line mkd. W. C.	
59.77	Set trial 1/16 cor. on line.	
79.88	SW cor. of sec. 15.	