

1st Standard Parallel N. R. 29 E., W.M.

Chains		Feet
40.00	Set post for $\frac{1}{4}$ Sec. cor. in mound of earth, trench and pits as per instructions.	
80.00	Set post for cor. to Secs. 32 & 33 in mound of earth, trench and pits as per instructions. Soil; poor and sandy, grass light, Country rolling.	
X	W. on S. Bdy. of Sec. 32 Var. 18° E.	
40.00	Set post for $\frac{1}{4}$ Sec. cor. in mound of earth, trench and pits as per instructions.	
80.00	Set post for cor. to Secs. 31 & 32 in mound of earth trench and pits as per instructions. Soil; poor and sandy, grass light. A little greasewood and cactus. Level.	
X	W. on S. Bdy. of Sec. 31. Var. 18° E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor. in mound of earth trench & pits as per instructions.	
80.00	Set post for cor. to Tps. No. 5, N. of Rgs. 28 & 29 E., in mound of earth, trench and pits as per instructions. Land; gently rolling. Soil; land very poor. Dense growth of sage, intersperces with a little grass, greasewood and cactus. Land; gently rolling	
Exterior Bdy of Tp. 4 N., R. 29 E., W.M. As surveyed by Wm. B. Campbell, U.S. Deputy Surveyor Under Contract No. 95 Dated Sept. 19, 1860.		
N. bet. Secs. 31 & 36 Var. 20° 15' E.		
23.00	Commence to descend hill	
37.00	To foot of hill	
40.00	Set a post for $\frac{1}{4}$ sec. cor., drove charred stake & raised mound of earth as per instructions	
80.00	Set a post for cor. to Secs. 30, 31, 25, 36. Drove a charred	