

Subdivisional Lines of T. 4 N., R. 29 E., W.M.  
 As surveyed by T. W. Davenport, U.S. Deputy Surveyor  
 Under Contract No. 101  
 Dated Aug. 5, 1861

Chains		Feet
	N. bet. Secs. 35 & 36	
		Var. 20° 30' E.
40.00	Set $\frac{1}{4}$ Sec. post in mound with charred stake as per instructions.	
80.00	Set post in mound with charred stake as per instructions. Cor. to Secs. 25, 26, 35 & 36. Surface; undulating, Soil; sandy, productions, young and scattering sage, & bunch grass.	
<hr/>		
	Thence	
	E. on random bet. Secs. 36 & 25	
		Var. 20° 15' E.
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.70	Intersect E. Bdy. of the T., 30 lks. N. of Cor. to Secs. 25 & 36, from which N. 89° 47' W. on true line	
15.72	Commence to ascend ridge	
19.22	Top of ridge	
40.35	Set post for $\frac{1}{4}$ Sec. Cor. in mound with charred stake as per instructions.	
80.70	To Cor. of Sec. 25, 26, 35 & 36	
<hr/>		
	N. bet. Secs. 25 & 26	
		Var. 20° 15' E.
23.00	To foot of ridge	
30.00	Top of ridge	
38.00	Foot of ridge on flat	
40.00	Set $\frac{1}{4}$ Sec. post in mound with charred stake, as per in- structions.	
80.00	Set post, in mound with charred stake, as per instructions. Cor. to Secs. 23, 24, 25 & 26 Land; undulating, Sandy, sparsely covered with bunch grass.	