

Subdivisional Lines of T. 4 N., R. 29 E., W.M.

Chains		Feet
80.00	Set post in mound with charred stake as per instructions. Cor. to Secs. 22, 23, 26 & 27 Land; flat and sandy, producing sage, greasewood, Cactus, dwarf Sun flower and bunch grass.	
	<hr/> E. on random bet. Secs. 23 & 26 <div style="text-align: right;">Var. 20° 30' E</div>	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.07	Intersect N. and S. line, 25 lks. S. of the Sec. Cor. S. 89° 49' W. on true line bet. Secs. 23 & 26	
40.03 $\frac{1}{2}$	Set $\frac{1}{4}$ Sec. Cor. post in mound with charred stake as per instructions.	
80.07	To Cor. of Secs. 22, 23, 26 & 27 Soil and surface as before.	
	<hr/> N. bet. Secs. 22 & 23 <div style="text-align: right;">Var. 20° 31' E.</div>	
40.00	Set $\frac{1}{4}$ Sec. Cor. post in mound with charred stake as per instructions.	
80.00	Set post in mound with charred stake as per instructions. Cor. to Secs. 14, 15, 22 & 23 Surface; undulating, very sandy with sage, cactus etc.	
	<hr/> E. on random bet. Secs. 14 & 23 <div style="text-align: right;">Var. 20° 45' E.</div>	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.23	Intersect N. and S. line, 50 lks. S. of Sec. Cor. S. 89° 39' W. on true line bet. Secs. 14 & 23	
40.11 $\frac{1}{2}$	Set $\frac{1}{4}$ Sec. Cor. post in mound with charred stake as per instructions.	
80.23	To Cor. of Secs. 14, 15, 22 & 23 Soil & surface as in the preceding mile.	
	<hr/> N. bet. Secs. 14 & 15 <div style="text-align: right;">Var. 20° 45' E.</div>	
40.00	Set $\frac{1}{4}$ Sec. Cor. post in mound with charred stake as per	