

Subdivisional Lines of T. 4 N., R. 29 E., W.M.

Chains		Feet
	instructions.	
80.00	Set post in mound with charred stake as per instructions. Cor. to Secs. 10, 11, 14 & 15 Soil & surface as in the preceeding mile.	
	E. on random bet. Secs. 11 & 14 Var. 20° 30' E	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.25	Intersect N. & S. line, 40 lks. S. of Cor. to Secs. 11, 12, 13 & 14, thence S. 89° 43' W. on true line bet. Secs. 11 & 14	
40.12 $\frac{1}{2}$	Set $\frac{1}{4}$ Sec. Cor. post in mound with charred stake as per instructions.	
80.25	To Cor. of Secs. 10, 11, 14 & 15 Soil & surface as in the last mile.	
	N. bet. Secs. 10 & 11 Var. 20° 30' E.	
10.00	Top of rise	
40.00	Set $\frac{1}{4}$ Sec. Cor. post in mound with charred stake as per instructions. Foot of rise	
80.00	Set post in mound with charred stake as per instructions. Cor. to Secs. 2, 3, 10 & 11.	
	E. on random bet. Secs. 2 & 11 Var. 20° 30' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.80	Intersect N. & S. line, 50 lks. S. of Sec. Cor. S. 89° 39' W. on true line bet. Secs. 2 & 11	
39.90	Set $\frac{1}{4}$ Sec. Cor. post in mound with charred stake as per instructions.	
79.80	To Cor. of Secs. 2, 3, 10 & 11 Soil; sandy Surface; undulating productions, sage, greasewood, cactus, Yarrow, dwarf Sun flower and bunch grass.	