

## Subdivisional Lines of T. 4 N., R. 29 E., W.M.

Chains		Feet
	E. on random bet. Secs. 22 & 27.	
		Var. 20° 45' E.
40.00	Set temp. $\frac{1}{4}$ Sec. post At foot of table	
79.80	Intersect N. and S. line at Sec. Cor.	
	W. on true line bet. Secs. 22 & 27	
39.80	Set $\frac{1}{4}$ Sec. Cor. post in mound with charred stake as per instructions	
79.80	To Cor. of Secs. 21, 22, 27 & 28 Soil; sandy, with Sage, Greasewood, Cactus, etc.	
<hr/>		
	N. bet. Secs. 21 & 22	
		Var. 20° 45' E
40.00	Set $\frac{1}{4}$ Sec. Cor. post in mound with charred stake as per instructions.	
80.00	Set post, in mound with charred stake as per instructions. Cor. to Secs. 15, 16, 21 & 22 Soil; sandy Surface; undulating with Sage, bunch grass, etc.	
<hr/>		
	E. on random bet. Secs. 15 & 22	
		Var. 20° 30' E.
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.00	Intersect N. and S. line, 35 lks. N. of Sec. Cor. N. 89° 45' W. on true line bet. Secs. 15 & 22 Commence ascending	
40.00	Set $\frac{1}{4}$ Sec. Cor. post in mound, charred stake as per instructions.	
50.00	Mt. St. Helen, brs. E. 76° W. Mt. Rainier, brs. N. 59 $\frac{1}{2}$ ° W.	
80.00	To Cor. of Secs. 15, 16, 21 & 22. Soil; surface & productions as in the preceding mile	
<hr/>		
	N. bet. Secs. 15 & 16	
		Var. 20° 30' E.
40.00	Set $\frac{1}{4}$ Sec. Cor. post in mound with charred stake as per	