

Subdivisional Lines of T. 4 N., R. 30 E., W.M.

Chains		Feet
79.50	Cor. to Secs. 1, 2, 11 & 12 Land; level Soil; good	
23.50	The Closing Cor. being in sight, run N. on true line bet. Secs. 1 & 2 Ravine, 4.00 Chs. wide W.	
40.00	Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
73.44	Intersect N. line, Tp. 4 N., (Standard Parallel) at post Cor. to Secs. 35 & 36, T. 5 N., R. 30 E., and Secs. 1 & 2, T. 4 N., R. 30 E. Land; uneven Soil; 2nd rate.	
40.00	Sept. 8th N. on line bet. Secs. 34 & 35 Var. 21° E. Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set charred stake, with mound, trench and pits as per instructions, for Cor. to Secs. 26, 27, 34 & 35 Var. 20° 30' E. Soil; 1st rate.	
40.00	E. on random bet. Secs. 26 & 35 Set temp. $\frac{1}{4}$ Sec. post	
79.27	Intersect Sec. line, 20 lks. S. of Cor. to Secs. 25, 26, 35 & 36 S. 89° 51' W. on true line bet. Secs. 26 & 35	
39.63	Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
79.27	Cor. to Secs. 26, 27, 34 & 35 Soil; 1st rate.	