

## Subdivisional Lines of T. 4 N., R. 30 E., W.M.

Chains		Feet
80.00	instructions, for $\frac{1}{4}$ Sec. Cor. Cor. to Secs. 14, 15, 22 & 23. Soil; 2nd rate.	
40.00	N. on line bet. Secs. 14 & 15 Set charred stake, with mound, trench & pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set charred stake, with mound, trench and pits as per instructions, for Cor. to Secs. 10, 11, 14 & 15 Var. 20° E. Soil; 2nd rate.	
40.00	E. on random bet. Secs. 11 & 14 Set temp. $\frac{1}{4}$ Sec. post	
80.40	Intersect Sec. line, 12 lks. N. of Cor. to Secs. 11 & 12, 13 & 14	
40.20	N. 89° 55' W. on true line bet. Secs. 11 & 14 Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.40	Cor. to Secs. 10, 11, 14 & 15 Soil; 2nd rate.	
40.00	September 9 N. on line bet. Secs. 10 & 11 Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set charred stake, with mound, trench and pits as per instructions, for Cor. to Secs. 2, 3, 10 & 11. Var. 19° 54' E. Land; sandy, 2nd rate soil Soil; 2nd rate.	
40.25	Closing Cor. being in sight, run E. on true line bet. Secs. 2 & 11 Set charred stake, with mound, trench & pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	