

Subdivisional Lines of T. 4 N., R. 30 E., W.M.

Chains		Feet
	N. on line bet. Secs. 15 & 16	
5.00	Indian Trail, N. 45° W.	
6.50	Middle of Ravine, 4.00 Chs. wide, N. 45° W.	
40.00	Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set charred stake, with mound, trench and pits as per instructions, for Cor. to Secs. 9, 10, 15 & 16 Var. 20° 30' E. Bottom of Ravine, sandy 3rd rate.	
	<hr/>	
	E. on random bet. Secs. 10 & 15	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.85	Intersect Sec. line, 32 lks. S. of Cor. to Secs. 10, 11, 14 & 15 S. 89° 45' W. on true line bet. Secs. 10 & 15	
39.92	Set charred stake, with mound, trench & pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
79.85	Cor. to Secs. 9, 10, 15 & 16	
	<hr/>	
	N. on line bet. Secs. 9 & 10	
40.00	Set charred stake, with mounds, trench & pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set charred stake, with mound, trench and pits as per instructions, for Cor. to Secs. 3, 4, 9 & 10 Var. 20° 21' E. Soil; 2nd rate.	
	<hr/>	
	E. on random bet. Secs. 3 & 10	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.70	Intersect Sec. line, 40 lks. S of Cor. to Secs. 2, 3, 10 & 11 S. 89° 42' W. on true line bet. Secs. 3 & 10	
39.85	Set charred stake, with mound, trench & pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
79.70	Cor. to Secs. 4, 3, 9 & 10 Land; rolling.	