

First Standard Parallel N., bet. T 4 & 5, R 31 E. (N.Bdy.)

Chains		Feet
	<p>Good grass</p> <p>Soil; 2nd rate.</p> <hr/> <p>Resurvey of the Exterior Bdys. of T. 5 N., R. 31 E., W.M. As surveyed by Nicholas O. Walden, U.S. Deputy Surveyor Under Contract No. 209 Dated July 6, 1874.</p> <hr/> <p>From the Standard Cor. to Tp. 5 N., Rgs. 30 & 31 E.</p> <p>I run</p> <p>E. on blank line along the S. Bdy. of Sec. 31, T 5 N R 31 E</p>	
40.23	A point, 86 lks. N. of the $\frac{1}{4}$ Sec. Cor.	
80.00	" " 23 lks. W. and 86 lks. N. of the Cor. to Secs. 31 & 32	
	<hr/> <p>E on a blank line along the S. Bdy. of Sec. 32</p>	
40.35	A point, 180 lks. N. of the $\frac{1}{4}$ Sec. Cor.	
80.00	" " 69 lks. W. and 305 lks. N. of the Cor. to Secs. 32 & 33.	
	<hr/> <p>E. on a blank line along the S. Bdy. of Sec. 33</p>	
41.08	A point, 338 lks. N. of the $\frac{1}{4}$ Sec. Cor.	
80.00	" " 139 lks. W. and 364 lks. N. of the Cor. to Secs. 33 & 34.	
	<hr/> <p>E. on a blank line along the S. Bdy. of Sec. 34</p>	
41.67	A Point, 364 lks. N. of the $\frac{1}{4}$ Sec. Cor.	
80.00	" " 162 lks. W. and 364 lks. N. of the Cor. to Secs. 34 & 35	
	<hr/> <p>E. on blank line along the S. Bdy. of Sec. 35</p>	
44.98	A point, 485 lks. N. of the $\frac{1}{4}$ Sec. Cor.	
80.00	" " 210 lks. W. and 621 lks. N. of the Cor. to Secs. 35 & 36	
	<hr/> <p>E. on a blank line along the S. Bdy. of Sec. 36</p>	
42.43	A point, 717 lks. N. of the $\frac{1}{4}$ Sec. Cor. Oct. 24th 1874.	
80.74	A point, 807 lks. N. of the Cor. to Epc5 N., R 31 & 32 E.	