

Subdivisional Lines of T. 4 N., R. 31 E., W.M.

Chains		Feet
	Soil; 2nd rate.	
	<hr/>	
	N. bet. Secs. 1 & 2	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; on summit of ridge, course S.W., drove charred stake, dug pits and raised mound as per instructions.	
80.50	Intersect first Standard Parallel N., 10 lks. W. of post Cor. fo Secs. 35 & 36, T 5 N R 31 E. At point of intersection, set post Closing Cor. for Secs. 1 & 2, drove charred stake, dug pits and raised mound as per instructions. Land; broken, grass good Soil; 2nd rate.	
		August 9th, 1866.
	<hr/>	
	N. bet. Secs. 34 & 35	
16.50	Botton of ravine, course N.W.	
40.00	Set basalt stone, 5 x 8 x 12, cor. for $\frac{1}{4}$ Sec.	
80.00	Set post Cor. for Secs. 26, 27, 34 & 35; drove charred stake, dug pits and raised mound as per instructions. Land; broken, grass excellent Soil; 2nd rate.	
	<hr/>	
	E. on random bet. Secs. 26 & 35	
		Var. 20'30' E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.68	Intersected N. & S. line at post Cor. W. on true line	
39.84	Set $\frac{1}{4}$ Sec. Cor. post; drove charred stake, dug pits and raised mound as per instructions.	
79.68	To post Cor., & raised mound as per instructions Land; broken, grass good Soil; 2nd rate.	
	<hr/>	
	N. bet. Secs. 26 & 27	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits	