

Subdivisional Lines of T. 4 N., R. 31 E., W.M.

| Chains | | Feet |
|--------|---|------|
| | and raised mound as per instructions. | |
| 44.00 | Bottom of ravine, course N.W. | |
| 30:00 | Set post Cor. for Secs. 22, 23, 26 & 27, drove charred stake, dug pits and raised mound as per instructions. Land; broken, good grass Soil; 2nd rate. | |
| <hr/> | | |
| | E. on random bet. Secs. 23 & 26 Var. 21° E. | |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. post Cor. | |
| 79.74 | Intersected N. & S. line, 22 lks. S. of post Cor. S. 89° 51' W. on true line | |
| 39.87 | Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits & raised mound as per instructions. | |
| 79.74 | To post Cor. Land; broken, good grass Soil; 2nd rate. | |
| <hr/> | | |
| | N. bet. Secs. 22 & 23 | |
| 40.00 | Set post, on summit of ridge, for $\frac{1}{4}$ Sec. Cor.; drove charred stake, dug pits and raised mound as per instructions. | |
| 81.00 | Set post Cor. for Secs. 14, 15, 22 & 23. Land slopes to the W.; drove charred stake, dug pits and raised mound as per instructions. Land; broken, good grass. Soil; 2nd rate. | |
| <hr/> | | |
| | E. on random bet. Secs. 14 & 23 Var. 20°30' E. | |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. post Cor. | |
| 79.76 | Intersect N. & S. line, 36 lks. S. of post Cor. S. 89° 45' W. on true line | |
| 33.00 | Stage Road, course N.W. | |
| 39.88 | Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits & raised mound as per instructions. | |