

## Subdivisional Lines of T. 4 N., R. 31 E., W.M.

Chains		Feet
	E. on random bet. Secs. 15 & 22	
		Var. 20°30' E.
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
79.90	Intersected N. & S. line, 18 lks. N. of post Cor.	
	N. 89° 52' W. on true line	
39.95	Set post Cor. for $\frac{1}{4}$ Sec. on land facing the E.; drove charred stake, dug pits and raised mound as per instructions.	
79.90	To post Cor.	
	Land; broken, grass good	
	Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 15 & 16	
40.00	Set post cor. for $\frac{1}{4}$ Sec. in the head of the ravine on steep hill-side facing the N.E.; drove charred stake, dug pits and raised mound as per instructions.	
74.50	Stage Road, course N.W. & S.E.	
80.00	Set post Cor. for Secs. 9, 10, 15 & 16; drove charred stake, dug pits and raised mound as per instructions.	
	Land; broken, good grass	
	Soil; 2nd rate.	
<hr/>		
	E. on random bet. Secs. 10 & 15	
		Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor. post	
80.15	Intersect N. & S. line, 26 lks. N. of post Cor.	
	N. 89° 49' W. on true line	
40.07	Set post Cor. for $\frac{1}{4}$ Sec.; in bottom of ravine, course S.W.; drove charred stake, dug pits and raised mound as per instructions.	
80.15	To post Cor.	
	Land; broken	
	Grass good	
	Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 9 & 10	
40.00	Set post Cor. for $\frac{1}{4}$ Sec., on land sloping to the S.W.; drove	