

Subdivisional Lines of T. 4 N., R. 31 E., W.M.

Chains		Feet
	charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 3, 4, 9 & 10, on level, drove charred stake, dug pits and raised mound, as per instructions. Land; broken, grass good Soil; 2nd rate.	
<hr/>		
	E. on random bet. Secs. 3 & 10	Var. 20° E.
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
80.28	Intersected N. & S. line, 34 lks. N. of post Cor. N. 89° 45' W. on true line	
40.14	Set post Cor. for $\frac{1}{4}$ Sec., on land sloping to the W.; drove charred stake, dug pits and raised mound as per instructions.	
80.28	To post Cor. Land; broken Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 3 & 4	
40.00	Set $\frac{1}{4}$ Sec. post Cor.; drove charred stake, dug pits and raised mound as per instructions.	
80.05	Intersected 1st Standard Parallel N., 28 lks. W. of post Cor. for Secs. 33 & 34, T 5 N R 31 E., at point of inter section, set post Closing Cor. for Secs. 3 & 4; drove charred stake, dug pits and raised mound as per instructions. Land; broken grass good Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 32 & 33	
40.00	Set post Cor. for $\frac{1}{4}$ Sec., on land sloping to the N.W.; drove charred stake, dug pits and raised mound as per instructions.	

August 11th, 1866.