

Subdivisional Lines of T. 4 N., R. 31 E., W.M.

Chains		Feet
59.00	Bottom of ravine, course N.W.	
80.00	Set post Cor. for Secs. 28, 29, 32 & 33, on land sloping to the S.; drove charred stake, dug pits, and raised mound as per instructions.	
	Land; broken, grass good	
	Soil; 2nd rate.	
<hr/> E. on random bet. Secs. 28 & 33		
		Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sect. post Cor.	
79.88	Intersected N. & S. line, 52 lks. N. of post Cor. N. 89° 38' W. on true line	
28.00	Summit of ridge, course S.W.	
39.94	Set post Cor. for $\frac{1}{4}$ Sec., on side of small ravine, course S.W.; drove charred stake, dug pits and raised mound as per instructions.	
79.88	To post Cor.	
	Land; broken, good grass	
	Soil; 2nd rate.	
<hr/> N. bet. Secs. 28 & 29		
40.00	Set post Cor. for $\frac{1}{4}$ Sec., on S. slope of ravine, drove charred stake, dug pits and raised mound as per instructions.	
60.00	Bottom of Ravine, course N.W.	
80.00	Set post Cor. for Secs. 20, 21, 28 & 29, on land facing the N.W.	
	Land; broken, good grass	
	Soil; 2nd rate.	
<hr/> E. on random bet. Secs. 21 & 28		
		Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
79.92	Intersected N. and S. line, 61 lks. N. of post Cor. N. 89° 34' W. on true line.	