

Subdivisional Lines of T. 4 N., R. 31 E., W.M.

Chains		Feet
39.61	Set post Cor. for $\frac{1}{4}$ Sec. on land gently sloping to the N.; drove charred stake, dug pits and raised mound as per instructions.	
79.61	To post Cor. Land; broken, good grass Soil; 2nd rate.	
N. bet. Secs. 29 & 30		
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
42.50	Bottom of ravine, course N.W.	
80.00	Set post Cor. for Secs. 19, 20, 29 & 30, on level, drove charred stake, dug pits and raised mound as per instruc- tions.	
	Land; broken, good grass Soil; 2nd rate.	
E. on random bet. Secs. 20 & 29		
		Var. 20° E.
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
80.22	Intersected N. & S. line, 55 lks. N. of post Cor. N. 89° 36' W. on true line	
40.11	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.22	To post Cor. Land; broken, good grass Soil; 2nd rate.	
W. on random bet. Secs. 19 & 30		
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
79.56	Intersected N. and S. line, 12 lks. N. of post Cor. N. 89° 55' E. on true line	
39.56	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
79.56	To post Cor. Land; broken, grass good	