

Subdivisional Lines of T. 4 N., R. 31 E., W.M.

Chains		Feet
	Soil; 2nd rate.	
	<hr/>	
	N. bet. Secs. 19 & 20	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 17, 18, 19 & 20	
	Land; broken, good grass	
	Soil; 2nd rate.	
	<hr/>	
	E. on random bet. Secs. 17 & 20	
		Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
80.27	Intersected N. and S. line, 48 lks. N. of post Cor.	
	N. 89° 39' W. on true line	
40.18	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.27	To post Cor.	
	Land; broken, grass good	
	Soil; 2nd rate.	
	<hr/>	
	W. on random bet. Secs. 18 & 19	
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
79.52	Intersected N. & S. line, 22 lks. N. of post Cor.	
	N. 89° 51' E. on true line	
39.52	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
79.52	To post Cor.	
	Land; broken, good grass	
	Soil; 2nd rate.	
		August 13, 1866.
	<hr/>	
	N. bet. Secs. 17 & 18	
40.00	Set post Cor. for $\frac{1}{4}$ Sec. in gulch, course N.W.	
80.00	Set post Cor. for Secs. 7, 8, 17 & 18, on level, drove charred stake, dug pits and raised mound as per instructions.	