

## Subdivisional Lines of T. 4 N., R. 32 E., W.M.

Chains		Feet
80.00	Set post Cor. for Secs. 13, 14, 23 & 24; drove charred stake dug pits and raised mound as per instructions. Land; broken Grass Good Soil; 2nd rate.	
<hr/> E. on random bet. Secs. 13 & 24, T. 4 N., R. 32 E.		
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.58	Intersect N. & S. Tp. line, 60 lks. N. of post, from which I run N. $89^{\circ} 35'$ W. on true line	
39.79	Set $\frac{1}{2}$ Sec. post on hillside, sloping to Spring Hollow.	
60.00	To Spring Hollow, course S.W.	
79.58	To post Cor. Land; broken Grass good Soil; 2nd rate.	
<hr/> N. bet. Secs. 13 & 14, T. 4 N., R. 32 E. Var. $20^{\circ} 30'$ E.		
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 11, 12, 13 & 14; drove charred stake, dug pits and raised mound as per instructions. Land; rolling Grass good Soil; good 2nd rate.	
<hr/> E. on random bet. Secs. 12 & 13, T. 4 N., R. 32 E.		
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.50	Intersect N. & S. Tp. line, 40 lks. N. of post, from which I run N. $89^{\circ} 42'$ W. on true line	
40.25	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
80.50	To post Cor.	