

Subdivisional Lines of T. 4 N., R. 32 E., W.M.

Chains		Feet
	May 2, 1865	
	N. bet. Secs. 34 & 35, T. 4 N., R. 32 E.	
	Var. 20° 30' E.	
40.00	Set $\frac{1}{4}$ Sec. post in head of gully, sloping N.W.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 26, 27, 34 & 35. Drove charred stake, dug pits and raised mound as per instructions. Land; rolling Grass good Soil; 2nd rate.	
	<hr/>	
	E. on random bet. Secs. 26 & 35, T. 4 N., R. 32 E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.20	Intersect N. & S. line, 5 lks. N. of post, from which I run N. 89° 58' W. on true line	
40.10	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits & raised mound as per instructions.	
80.20	To post Cor. Land; rolling Grass good Soil; 2nd rate.	
	<hr/>	
	N. bet. Secs. 26 & 27, T. 4 N., R. 32 E.	
	Var. 20° 30' E.	
40.00	Set $\frac{1}{4}$ Sec. post in head of Gully, sloping to the N.E.; drove charred stake, dug pits & raised mound as per instructions.	
80.00	Set post cor. for Secs. 22, 23, 26 & 27, bet. two ridges sloping to the N.E.; drove charred stake, dug pits & raised mound as per instructions. Land; rolling Grass good Soil; 2nd rate.	